| REVISION HISTORY | | | | | |
|---|---|---|---|---|---|
| Revision | Drawn by Date | Drawn by | Revision Description | Checked by Date | Checked by |
| | | | | | |



D-D
INSPECTION HATCH
( 1 : 20 )



TYPICAL WAY TO ATTACH THE ROOF TO A SHELL
(NOT IN SCALE)



A ( 1 : 50 )



( 1 : 30 )



B-B ( 1 : 50 )



E-E
N9 - OVERFLOW
( 1 : 15 )

HOLD





C-C ( 1 : 50 )



F-F ( 1 : 10 )


WALL MUST RESIST 1000 mm LIQUID LEVEL DIFFERENCE
ROUNDINGS FOR ALL OPENING CORNERS r = 50 mm
700
25
OPENING WITH HATCH
800
1700

FLAT PATTERN OF
OUTER AIR SEPARATION CYLINDER
( 1 : 100 )


WALL MUST RESIST 1000 mm LIQUID LEVEL DIFFERENCE
OPENING FOR N1.1
ROUNDINGS FOR ALL OPENING CORNERS r = 50 mm
300
700

FLAT PATTERN OF
INNER AIR SEPARATION CYLINDER
( 1 : 75 )



TANK ANCHORING



QUANTITY, SIZES AND DIMENSIONS OF ANCHOR BOLTS FROM SUPPLIER



FLANGE DRILLING DIRECTIONS
(UNLESS OTHERWISE NOTED)



## LIST OF CONNECTIONS

| ITEM | QTY | SIZE | PRESSURE CLASS | TYPE | ELEVATION | DIRECTION | DESCRIPTION | NOTE |
|---|---|---|---|---|---|---|---|---|
| N1.1 | 1 | DN300 | PN10 | PIPE | HOLD! | HOLD! | FILTRATE IN | 1° SLOPE (RISING TOWARDS TANK) |
| N1.2 | 1 | DN300 | PN10 | FLANGE | HOLD! | HOLD! | FILTRATE IN | 1° SLOPE (RISING TOWARDS TANK) |
| N2.1 | 1 | DN300 | PN10 | FLANGE | HOLD! | HOLD! | PUMP OUT | |
| N2.2 | 1 | DN200 | PN10 | FLANGE | HOLD! | HOLD! | PUMP OUT | |
| N5 | 1 | DN80 | PN40 | PAD FLANGE | HOLD! | HOLD! | INSTRUMENT | BLIND FLANGE, GASKET, STUD BOLTS AND NUTS INC. IN THE DELIV. |
| N6 | 1 | DN100 | PN10 | FLANGE | 0 | HOLD! | DRAIN | |
| N8 | 1 | DN300 | PN10 | FLANGE | HOLD! | - | VENT | |
| N9 | 1 | DN300 | PN10 | PIPE | HOLD! | HOLD! | OVERFLOW | |
| N11 | 1 | DN15 | PN10 | WN FLANGE | - | - | OVERFLOW WATER IN | |
| N12 | 1 | DN25 | PN10 | WN FLANGE | - | - | OVERFLOW DRAIN | |
| N13 | 1 | DN80 | PN10 | PIPE | - | - | OVERFLOW VENT | |
| MW | 1 | Ø600 | - | DAVIT TYPE | HOLD! | HOLD! | MANWAY | |
| IH | 1 | Ø500 | - | - | HOLD! | HOLD! | INSPECTION HATCH | HINGED, QUICK LOCK COVER, SAFETY GRATING, SEALED |
| GL | 4 | - | - | - | - | - | GROUNDING LUG | |
| NP | 1 | - | - | - | HOLD! | HOLD! | TANK NAMEPLATE | |

## TECHNICAL DATA

### STANDARDS, NORMS AND REGULATIONS

| | |
|---|---|
| Design Law | Local laws |
| Design Code | EN14015/API650 |
| Flange Standard | HOLD |

### EXTERNAL LOADS

| | |
|---|---|
| Wind Load | see project standards |
| Earthquake Load | see project standards |
| Snow Load | see project standards |
| External loads from piping | see project standards |
| Roof | 2 kN/m2 distributed load |

### DESIGN AND OPERATIONAL DATA

| | | DESIGN | VALUES | |
|---|---|---|---|---|
| | | Max | Min | |
| Pressure | kPa (g) | 2 + hydr. | -2 | |
| Temperature | °C | 100 | 0 | |
| Nominal Volume | m3 | 226 | | |
| Medium density of content | kg/m3 | 1050 | | |
| Contents | | Filtrate | | |

### MATERIALS

| Part | Material | Note |
|---|---|---|
| Main material | 1.4307 or Equal | |

### PAINTING SYSTEM AND COLOR

See project painting standard

### INSULATION

For person protect HOLD

| | | |
|---|---|---|
| Insulation Area | m² | - |
| Insulation Thickness | mm | - |
| Cladding Area | m² | - |
| Cladding Thickness | mm | - |

### NOTES

WALL THICKNESSES (ETC. DIMENSIONS) ARE INDICATIVE TO SET THE BASIS FOR ENGINEERING TANK MANUFACTURER IS RESPONSIBLE ON TANK STRENGTH AND THAT DEFORMATIONS CAUSED BY DYNAMIC AND STATIC LOADS ARE WITHIN GIVEN LIMITS REGARDLESS WHETHER THE VESSEL IS EMPTY OR LOADED

PRELIMINARY

| GENERAL TOLERANCES LINEAR DIMENSIONS | Nominal measure | >0.5 ≤3 | >3 ≤6 | >6 ≤30 | >30 ≤120 | >120 ≤400 | >400 ≤1000 | >1000 ≤2000 | >2000 ≤4000 | >4000 ≤8000 | >8000 ≤12000 | >12000 ≤16000 | >16000 ≤20000 | >20000 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| - Welding | ISO13920-B | ± 1 | ± 1 | ± 1 | ± 2 | ± 2 | ± 3 | ± 4 | ± 6 | ± 8 | ± 10 | ± 12 | ± 14 | ± 16 |
| - Machining | ISO 2768-m | ± 0.1 | ± 0.1 | ± 0.2 | ± 0.3 | ± 0.5 | ± 0.8 | ± 1.2 | ± 2 | ± 3 | ± 4 | ± 5 | ± 6 | – |
| - Chamfers and radius | ISO 2768-m | ± 0.2 | ± 0.5 | ± 1.0 | | | | | | | | | | |
| - Cutting, bending | ISO 2768-c | ± 0.2 | ± 0.3 | ± 0.5 | ± 0.8 | ± 1.2 | ± 2 | ± 3 | ± 4 | ± 5 | ± 6 | ± 7 | ± 8 | – |

- Flame cutting < ISO 9013-IIB / ISO 9013-IIG
- Casting, machine. ISO 8062-CT10
- Casting, handm. ISO 8062-CT12
- Forgings SFS 3507, DIN 7527

**ANGULAR DIMENSIONS**
- Welding ISO13920-B
- Machining ISO 2768-m
- Bending < ISO 2768-c s<4 / ISO 2768-v s>4

**SYMBOLS**
- Surface roughness ISO 1302-Ra
- Welding symbols ISO 2553
- Tolerancing ISO 8015

**GEOM.TOL.**
- Symbols ISO 1101
- Welding ISO 13920-G
- Machining ISO 2768-K

**MISCELLANEOUS**
- Welding class C (min.), EN ISO 5817

| | | | | | | |
|---|---|---|---|---|---|---|
| Customer | | AMC | Basic Material Name | | Basic Material Standard | Net weight |
| Position No. | Customer Drawing No | Description Line 1 | | | Designed<br>J.Leino | Date<br>07.07.2026 |
| Product type | Product Code | Description Line 2 | | | Drawn | Date |
| Size<br>A1 | Scale<br>1:40 | Description Line 1 (EN)<br>DDW FILTRATE TANK | | | Checked | Date |
| Division / Prod. Home | System<br>INVENTOR | Description Line 2 (EN)<br>MAIN DIMENSIONAL DRAWING | | | Approved | Date |
| ANDRITZ | | Replacement for Drawing / Rev. | Replaced by Drawing / Rev. | | Copy from Drawing / Rev. | Sort |
| | | Item No. | Reference Drawing | | Old Drawing Number / Rev. | M-Film |
| | | SAP Main WBS Element | | | Drawing Number<br>900135359 / Rev. | Sheet<br>1 / 1 |

This document constitutes confidential and proprietary information of Andritz Companies. Any party accepting receipt of this document does so on the express understanding and agreement that it will neither reproduce, disclose to third parties or use this document for any purpose other than those expressly agreed to by any Andritz Company.